


AD-A068 674


NEW JERSEY STATE DEPT OF ENVIRONMENTAL PROTECTION TRENTON P78 1372
NATIONAL DAM SAFETY PROGRAM. MISHE - MOKWA DAM (NJ 00419); DELA--ETC(U)
MAY 79 R J MCDERMOTT
DACW61-78-C-0124
NL

UNCLASSIFIED

1 OF 2

AD
A068674





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD A068674

DELAWARE RIVER BASIN
HAYNES CREEK TRIBUTARY
BURLINGTON COUNTY
NEW JERSEY

MISHE - MOKWA DAM
NJ 00419

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

DDC FILE COPY,



Approved for public release;
distribution unlimited

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

May 79 1979

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DDC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|--|-----------------------|--|
| 1. REPORT NUMBER NJ 419 | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Mishe-Mokwa Dam Burlington County, N.J. | | 5. TYPE OF REPORT & PERIOD COVERED 9 FINAL / rept. |
| 6. AUTHOR(s) Richard J. McDermott, P.E. | | 7. PERFORMING ORG. REPORT NUMBER |
| 8. CONTRACT OR GRANT NUMBER(s) DACW61-78-C-0124 | | |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS Storch Engineering 220 Ridgedale Ave. Florham Park, N.J. 07932 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, Pennsylvania 19106 | | 12. REPORT DATE May 1979 |
| 13. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | | 14. NUMBER OF PAGES 93 |
| 15. SECURITY CLASS. (of this report) Unclassified | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited. | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) National Dam Safety Program, Mishe - Mokwa Dam (NJ 00419), Delaware River Basin, Haynes Creek Tributary, Burlington County, New Jersey. Phase I Inspection Report. | | |
| 18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia, 22151. | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams Safety Embankments Visual Inspection Spillway National Dam Inspection Report Structural Analysis Mishe-Mokwa Dam, N.J. | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report. | | |

410891



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE - 2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO

NAPEN-D

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, NJ 08621

7 MAY 1979

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Mishe-Mokwa Dam in Burlington County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Mishe-Mokwa Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's spillway is considered inadequate since 65 percent of the Spillway Design Flood - SDF - would overtop the dam. (The SDF, in this instance, is one half of the Probable Maximum Flood). To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980.

b. Within three months from the date of approval of this report, engineering studies and analyses should be performed to monitor the seepage by visual observation in order to determine its effect on the structural stability of the dam. If necessary, measurements should be made by the use of appropriate instrumentation. The monitoring should be performed on a monthly basis. A detailed topographic survey of the dam and the areas around the dam should also be made and become part of the permanent records of the dam. Remedial measures to correct the poten-

This document has been approved
for public release and sale; its
distribution is unlimited.

NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED US BY
THE SPONSORING AGENCY. ALTHOUGH IT
IS RECOGNIZED THAT CERTAIN PORTIONS
ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.

NAPEN-D

Honorable Brendan T. Byrne

tial inundation of the two houses adjacent to the low area in the beach should also be studied. Any remedial measures found necessary should be initiated within calendar year 1980.

c. The following remedial actions should be completed within six months from the date of approval of this report:

(1) Trees and brush on the dam embankment should be removed. Trees should be cut at the ground surface and brush removed in a way that will cause minimal disturbance to the embankment.

(2) The eroded areas on the dam embankment should be properly filled and compacted. The drainage system for the road should be corrected to prevent future erosion. Such work should be done immediately after the trees and brush have been removed.

(3) A good stand of grass should be established on all surfaces of the embankment.

(4) The concrete spillway and discharge culvert should be thoroughly inspected and repaired as required.

(5) The stilling basin area should be cleaned of accumulated debris.

The owner of the dam should initiate a program of periodic inspection and maintenance. A visual inspection of the dam and appurtenances should be made annually and reported on a standardized check list form. Repairs should be made when required and the following maintenance should be performed annually: remove vegetation from the embankment, fill any eroded surfaces of the embankment and clear the downstream channel. In addition, the practice of lowering the lake annually for maintenance purposes should be continued and at least once every five years the submerged portions of the dam and spillway should be inspected and repaired while the lake is drawn down.

| | |
|-----------------------|---|
| ACCESSION for | |
| NTIS | White Section <input checked="" type="checkbox"/> |
| DDC | Buff Section <input type="checkbox"/> |
| UNANNOUNCED | <input type="checkbox"/> |
| RES. LOCATION | |
| BY | |
| POSTMASTER: RETURN TO | |
| SPECIAL | |
| R | 23 |

NAPEN-D


Honorable Brendan T. Byrne

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Edwin B. Forsythe of the Sixth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



JAMES G. TON
Colonel, Corps of Engineers
District Engineer

1 Incl
As stated

Copies furnished:

Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N. J. Dept. of Environmental Protection
P. O. Box CN029
Trenton, NJ 08625

John O'Dowd, Acting Chief
Bureau of Flood Plain Management
Division of Water Resources
N. J. Dept. of Environmental Protection
P. O. Box CN029
Trenton, NJ 08625

MISHE-MOKWA DAM (N100419)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 12 December 1978 by Storch Engineers under contract to the State of New Jersey. The State, under agreement with the U. S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Mishe-Mokwa Dam, a high hazard potential structure, is judged to be in fair overall condition. The dam's spillway is considered inadequate since 65 percent of the Spillway Design Flood - SDF - would overtop the dam. (The SDF, in this instance, is one half of the Probable Maximum Flood). To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980.

b. Within three months from the date of approval of this report, engineering studies and analyses should be performed to monitor the seepage by visual observation in order to determine its effect on the structural stability of the dam. If necessary, measurements should be made by the use of appropriate instrumentation. The monitoring should be performed on a monthly basis. A detailed topographic survey of the dam and the areas around the dam should also be made and become part of the permanent records of the dam. Remedial measures to correct the potential inundation of the two houses adjacent to the low area in the beach should also be studied. Any remedial measures found necessary should be initiated within calendar year 1980.

c. The following remedial actions should be completed within six months from the date of approval of this report:

(1) Trees and brush on the dam embankment should be removed. Trees should be cut at the ground surface and brush removed in a way that will cause minimal disturbance to the embankment.

(2) The eroded areas on the dam embankment should be properly filled and compacted. The drainage system for the road should be corrected to

prevent future erosion. Such work should be done immediately after the trees and brush have been removed.

(3) A good stand of grass should be established on all surfaces of the embankment.

(4) The concrete spillway and discharge culvert should be thoroughly inspected and repaired as required.

(5) The stilling basin area should be cleaned of accumulated debris.

The owner of the dam should initiate a program of periodic inspection and maintenance. A visual inspection of the dam and appurtenances should be made annually and reported on a standardized check list form. Repairs should be made when required and the following maintenance should be performed annually: remove vegetation from the embankment, fill any eroded surfaces of the embankment and clear the downstream channel. In addition, the practice of lowering the lake annually for maintenance purposes should be continued and at least once every five years the submerged portions of the dam and spillway should be inspected and repaired while the lake is drawn down.

APPROVED: _____

JAMES G. TON
Colonel, Corps of Engineers
District Engineer

DATE: _____

2 May 1979

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

| | |
|---------------------|-------------------------------|
| Name of Dam: | Mishe-Mokwa Dam, I.D. NJ00419 |
| State Located: | New Jersey |
| County Located: | Burlington |
| Drainage Basin: | Delaware |
| Stream: | Tributary to Haynes Creek |
| Date of Inspection: | December 12, 1978 |

Assessment of General Condition of Dam

Based on visual inspection, past operational performance and Phase I engineering analyses, Mishe-Mokwa Dam is assessed as being in fair overall condition.

Hydraulic and hydrologic analyses indicate that the spillway is inadequate. Discharge from the spillway and from a low area of the lake shore adjacent to the dam is not sufficient to pass the designated spillway design flood (SDF) without overtopping of the dam. (The SDF for Mishe-Mokwa Dam is equal to one-half the probable maximum flood.) The spillway, together with the low area adjacent to the dam, can pass approximately 32 percent of the probable maximum flood. Therefore, the owner should engage a qualified professional engineer soon to perform accurate hydraulic and hydrologic analyses relating to the spillway capacity. Based on the findings of the analyses, the dam and spillway should be modified to prevent overtopping of the dam resulting from a storm equivalent to the SDF.

Two zones of seepage are present on the downstream face and toe of embankment. Arrangements should be made soon to monitor the seepage on a monthly basis in order to determine its effect on the structural stability of dam.

Two houses appear to be located in the downstream flood plain of the low area adjacent to the dam. Any discharge from the lake over the low area could effect the two houses. Remedial measures to correct this condition should be initiated soon.

The spillway appears to be in good condition. However, in the near future, it should be thoroughly inspected and renovated by sand blasting, grouting where needed and coating with epoxy.

The spillway discharge culvert, although appearing structurally sound, contains some deterioration which should be repaired in the near future.

The stilling basin downstream of the spillway discharge culvert contains debris that should be removed in the near future.


The embankment is generally free of settlement and appears to be structurally sound. However, trees and brush as well as erosion are present on its surface. These conditions should be repaired in the near future and thereafter maintained. Repairs include the removal of trees and brush, the filling of eroded areas, the establishment of a grass cover and the correction of the roadway drainage system.

The owner should, in the near future, implement a program of periodic inspection and maintenance for the dam which would include a topographic survey to provide a record of existing conditions. Repairs should be made when required and the following maintenance should be performed annually: remove trees and brush from the embankment,

fill any eroded surfaces of the embankment and clear the downstream channel. In additon, the practice of lowering the lake annually for maintenance purposes should be continued and at least once every five years the submerged portions of the dam and spillway should be inspected and repaired while the lake is drawn down.

Richard J. McDermott

Richard J. McDermott, P.E.



OVERVIEW - MISHE - MOKWA DAM

12 DEC. 1978

TABLE OF CONTENTS

| | <u>Page</u> |
|---|-------------|
| ASSESSMENT OF GENERAL CONDITION OF DAM | i |
| OVERVIEW PHOTO | iv |
| TABLE OF CONTENTS | v |
| PREFACE | vii |
| SECTION 1 - PROJECT INFORMATION | 1 |
| 1.1 General | |
| 1.2 Description of Project | |
| 1.3 Pertinent Data | |
| SECTION 2 - ENGINEERING DATA | 9 |
| 2.1 Design | |
| 2.2 Construction | |
| 2.3 Operation | |
| 2.4 Evaluation | |
| SECTION 3 - VISUAL INSPECTION | 11 |
| 3.1 Findings | |
| SECTION 4 - OPERATIONAL PROCEDURES | 14 |
| 4.1 Procedures | |
| 4.2 Maintenance of Dam | |
| 4.3 Maintenance of Operating Facilities | |
| 4.4 Description of Warning System | |
| 4.5 Evaluation | |

TABLE OF CONTENTS (cont.)

| | <u>Page</u> |
|--|-------------|
| SECTION 5 - HYDRAULIC/HYDROLOGIC | 16 |
| 5.1 Evaluation of Features | |
| SECTION 6 - STRUCTURAL STABILITY | 19 |
| 6.1 Evaluation of Structural Stability | |
| SECTION 7 - ASSESSMENT AND RECOMMENDATIONS | 21 |
| 7.1 Dam Assessment | |
| 7.2 Recommendations | |
| PLATES | |
| 1 KEY MAP | |
| 2 VICINITY MAP | |
| 3 GEOLOGIC MAP | |
| 4 GENERAL PLAN | |
| 5 SPILLWAY PLAN & SECTION | |
| 6 PHOTO LOCATION PLAN | |
| APPENDICES | |
| 1 Check List - Visual Inspection | |
| Check List - Engineering Data | |
| 2 Photographs | |
| 3 Engineering Data | |
| 4 Hydrologic Computations | |
| 5 Bibliography | |

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 30214. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that the unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

MISHE-MOKWA DAM, I.D. NJ00419

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers to initiate a National Program of Dam Inspection throughout the United States. The Division of Water Resources of the New Jersey Department of Environmental Protection (NJDEP) in cooperation with the Philadelphia District of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the State of New Jersey. Storch Engineers has been retained by the NJDEP to inspect and report on a selected group of these dams. The NJDEP is under agreement with the Philadelphia District of the Corps of Engineers.

b. Purpose of Inspection

The visual inspection of Mishe-Mokwa Dam was made on December 12, 1978. The purpose of the inspection was to make a general assessment of the structural integrity and operational adequacy of the dam structure and its appurtenances.

1.2 Description of Project

a. Description of Dam and Appurtenances

Mishe-Mokwa Dam is an earthfill dam with a concrete box drop-inlet spillway. The spillway, which is covered with a metal grate, functions in both controlled and uncontrolled modes as follows: 1. the sides of the drop inlet form an uncontrolled weir and 2. a slot at the upstream end of the spillway is fitted with timber stoplogs forming a controlled weir. The embankment is sandy and grass covered with brush and trees on its downstream face and a paved road on its crest.

The stoplogs forming the controlled weir of the spillway can also be used as outlet works to drain the lake.

Having an overall crest length of 165 feet, the embankment extends southeast to a wooden dock beyond which a public beach extends along the northeast edge of Lake Mishe-Mokwa. The beach lies between the lake and the same road that runs along the dam crest. In the vicinity of the beach, the road elevation is approximately 0.9 feet above normal lake level while along the crest of dam the road elevation is approximately 2.1 feet above normal lake level. Thus, the lake shore is lower in the beach area than is the crest of dam, allowing high water levels to flow overland before overtopping the dam. A complete hydraulic analysis is contained in Appendix 4.

The spillway has dimensions 3.6' x 6.0' with stoplogs 2.4 feet long. Thus, the concrete weir crest length is 13.2 feet and the timber weir crest length is 2.4 feet. The spillway crest lies 2.3 feet below the elevation of the dam crest and 10.6 feet above the elevation of the downstream channel bottom.

Extending upstream of the main impoundment of Mishe-Mokwa Dam are three finger-like projections of water each of which consists of two or more impoundments separated by road embankments and connected by discharge structures similar to the subject spillway. The normal water level elevation of each impoundment is higher than that of its adjacent downstream impoundment, creating a "stepped" series of impoundments. A bypass channel has been constructed along the northwest shore of Lake Mishe-Mokwa connecting the first upstream stepped impoundment with the downstream channel of Mishe-Mokwa Dam. See Hydraulic computations, Appendix 4. A discharge structure at the downstream end of the bypass channel outlets to the downstream channel. This structure, together with its discharge pipe, is not considered to be an appurtenance of the dam.

A water pump is located on the downstream face of embankment near the stilling basin and is used at times of low flow to pump water from the stilling basin to one of the upstream impoundments to recharge the lake.

b. Location

Mishe-Mokwa Dam is located in the Borough of Medford Lakes, Burlington County, New Jersey. Also known as Beach 3 Dam, it impounds Lake Mishe-Mokwa which forms the recreation center of a densely populated section of Medford Lakes. Water outflowing from the dam passes into Ballinger Lake and then through a series of lakes and eventually into Haynes Creek. Principal access to the dam is provided by the local road forming its crest.

c. Size and Hazard Classification

Size and Hazard Classification criteria presented in "Recommended Guidelines for Safety Inspection of Dams," published by the U. S. Army Corps of Engineers are as follows:

SIZE CLASSIFICATION

| <u>Category</u> | <u>IMPOUNDMENT</u> | |
|-----------------|--------------------------|---------------------|
| | <u>Storage (Ac-Ft)</u> | <u>Height (Ft)</u> |
| Small | < 1000 and ≥ 50 | < 40 and ≥ 25 |
| Intermediate | ≥ 1000 and < 50,000 | ≥ 40 and < 100 |
| Large | $\geq 50,000$ | ≥ 100 |

HAZARD POTENTIAL CLASSIFICATION

| <u>Category</u> | <u>Loss of Life</u> | <u>Economic Loss</u> |
|-----------------|---|---|
| | (Extent of Development) | (Extent of Development) |
| Low | None expected (No permanent structures for human habitation) | Minimal (Undeveloped to occasional structures or agriculture) |
| Significant | Few (No urban developments and no more than a small number of inhabitable structures) | Appreciable (Notable agriculture, industry or structures) |
| High | More than few | Excessive (Extensive community, industry or agriculture) |

The characteristics of Mishe-Mokwa Dam are:

Storage = 54 acre-feet

Height = 13 feet

Potential Loss of Life: Approx. 25 homes within
1600 feet of dam in flood
plain as delineated by SDF
outflow.

Potential Economic Loss: Sewage treatment plant, two road
bridges within 3500 feet of dam.

Therefore, Mishe-Mokwa Dam is classified as "Small" size
and "High" hazard potential.

d. Ownership

Mishe-Mokwa Dam is owned by the Medford Lakes Colony
Club, Tecumsek Trail, Medford Lakes, New Jersey 08055.

e. Purpose of Dam

The purpose of the dam is the impoundment of a recreational
lake facility.

f. Design and Construction History

The dam reportedly was constructed prior to 1900 and
until approximately 1950 was used to impound cranberry
bogs. The residential development surrounding Lake
Mishe-Mokwa was constructed in or about 1950 and the

present concrete spillway was constructed approximately 10 years later. The contractor reportedly was the Hill Construction Company of Mt. Holly.

g. Normal Operational Procedures

The dam and appurtenances are maintained by Medford Lakes Colony Club while the road is maintained by the Borough of Medford Lakes. Regularly scheduled maintenance consists of the following: 1. Each spring the lake is lowered 3 to 4 feet at which time the gate is repaired, the lake cleaned and docks along the lake repaired. The lake lowering reportedly requires one week to accomplish. 2. Periodically, new turf is replaced where the embankment erodes away.

1.3 Pertinent Data

a. Drainage Area - 0.83 square miles

b. Discharge at Damsite

| | |
|---|------------|
| Maximum known flood at damsite | Unknown |
| Outlet works at pool elevation | 150 c.f.s. |
| Diversion tunnel low pool outlet at pool elevation | N.A. |
| Diversion tunnel outlet at pool elevation | N.A. |
| Gated spillway capacity at pool elevation | 0 c.f.s. |
| Gated spillway capacity at maximum pool elevation | 160 c.f.s. |
| Ungated spillway capacity at maximum pool elevation | N.A. |

| | |
|--|------------|
| Lake overflow (beach area) | 684 c.f.s. |
| Total spillway capacity at maximum pool elevation | 844 c.f.s. |

c. Elevation (Feet above MSL)

| | |
|---------------------------------|-----------------|
| Top of Dam | 72.4 |
| Maximum pool-design surcharge | 72.9 |
| Full flood control pool | N.A. |
| Recreation pool | 70.3 |
| Spillway crest | 70.1 |
| Lake overflow (beach area) | 71.2 |
| Stream bed at centerline of dam | 59.5 |
| Maximum tailwater | 63+ (Estimated) |

d. Reservoir

| | |
|------------------------------|------------------------|
| Length of maximum pool | 1,000 feet (irregular) |
| Length of recreation pool | 1,000 feet (irregular) |
| Length of flood control pool | N.A. |

e. Storage (Acre-feet)

| | |
|-------------------------------|--------------|
| Recreation pool | 27 acre-feet |
| Flood control pool | N.A. |
| Design surcharge (Elev. 72.9) | 61 acre-feet |
| Top of dam (Elev. 72.4) | 54 acre-feet |

f. Reservoir Surface (Acres)

| | |
|--------------------|----------------------|
| Top of dam | 14 acres (estimated) |
| Maximum pool | 15 acres (estimated) |
| Flood control pool | N.A. |
| Recreation pool | 11 acres |
| Spillway crest | 11 acres |

g. Dam

| | |
|-----------------------|---------------------|
| Type | Earthfill |
| Length | 165 feet |
| Height | 13 feet |
| Sideslopes - Upstream | 2 horiz. to 1 vert. |
| - Downstream | 2 horiz. to 1 vert. |
| Zoning | Unknown |
| Impervious core | Unknown |
| Cutoff | Unknown |
| Grout curtain | Unknown |

h. Diversion and Regulating Tunnel N.A.

i. Spillway

| | |
|--------------------|---------------------------------|
| Type | Drop Inlet |
| Length of weir | 15.6 feet |
| Crest elevation | 70.1 |
| Gates | Timber Stoplogs 2.4' long |
| Upstream channel | N.A. |
| Downstream channel | 3.5' x 4' conc. arch culvert |

j. Regulating Outlets

Timber stoplogs 2.4' long.

SECTION 2: ENGINEERING DATA

2.1 Design

No plans or calculations pertaining to either the original dam or the reconstructed spillway could be obtained.

2.2 Construction

No records are available pertaining to the construction of either the original dam or the reconstruction of the spillway in or about 1950.

2.3 Operation

No records of operation of the lake or dam are available. Normal operation of the dam and appurtenances reportedly consists of the following: 1. Water is pumped from the downstream channel of the dam to one of the impoundments upstream of the main lake to provide recharge during times of low flow. 2. The spillway stoplogs are pulled out each spring to lower the lake for maintenance purposes. The stoplogs are not pulled at the time of storm occurrences.

2.4 Evaluation

a. Availability

Engineering information pertaining to the design of either the original dam or the reconstruction of the spillway is not available.

The only engineering information available is the elevation of a bench mark located on the spillway headwall. The elevation, which appears to correspond to USGS datum, is on file at the Borough of Medford Lakes maintenance garage.

b. Adequacy

Available engineering data pertaining to Mishe-Mokwa Dam is not adequate to be of significant assistance to the performance of a Phase I evaluation. A list of absent information is included in paragraph 7.1.b.

c. Validity

The validity of engineering data cannot be assessed due to the absence of data.

SECTION 3: VISUAL INSPECTION

3.1 Findings

a. General

The inspection of Mishe-Mokwa Dam took place on December 12, 1978 by members of the staff of Storch Engineers. A copy of the visual inspection check list is contained in Appendix 1. The following procedures were employed for the inspection:

1. The embankment of the dam, appurtenant structures and adjacent areas were examined.
2. Areas of suspected seepage were noted and located.
3. The embankment and appurtenant structures were measured and key elevations at the first upstream impoundment were determined by hand level.
4. The embankment and appurtenant structures and adjacent areas were photographed.
5. A member of the maintenance staff of Medford Lakes Borough was present to assist in the inspection.

b. Dam

The dam embankment crest appeared to be level, with a slightly curved horizontal alignment. A paved road lies on the crest and was found to be in good condition.

Erosion was noted along sections of the upstream and downstream faces of the embankment, especially on the downstream face. No riprap was observed. Generally sandy in surface composition, the embankment contains some grass on its upstream face and grass, brush and trees on its downstream face.

Two seepage zones were noted on the downstream face of the embankment. A wet area was observed on the downstream face in the vicinity of the east wingwall of the discharge culvert. Seepage was observed at the embankment toe approximately 60 feet east of the spillway. Discharging in the form of a slight trickle, the seepage flows into a small drainage ditch running along the embankment toe into the stilling basin.

No evidence of cracking or settling was noted in the dam nor were any animal holes observed.

The generalized soils description of the dam site consists of stratified materials, predominantly silty sand and narrowly graded sand, deposited during the Tertiary period and designated on the Geologic map of New Jersey prepared by Lewis and Kummel as Kirkwood Sands. Composed on the average of varying percentages of very fine to coarse quartz sand, the Kirkwood Sands are overlain in the area of the lake by recently deposited stratified, swampy alluvium.

Bedrock is in excess of 100 feet below the ground surface. It is assumed that the dam is founded on the silty sands of the Kirkwood formation.

c. Appurtenant Structures

The crest of the spillway appeared uniformly aligned although a major part of it was submerged by overflow at the time of inspection. Water was flowing over the concrete weir section of the spillway and, therefore, the condition of much of the structure was not clearly observed. In general, the concrete as well as the steel grate and timber stoplogs appeared to be in good condition.

The spillway discharge culvert is generally in satisfactory condition although the concrete is deteriorated at its outlet end. The concrete of the discharge culvert headwall and wingwalls is in satisfactory condition with some minor cracks and spalls.

d. Reservoir Area

Lake Mishe-Mokwa is an irregularly shaped lake located in a densely populated residential area. Its shores range from less than 1% to 10% with an average slope of approximately 4%. A few docks are located along the edge of the lake where residential development has taken place. A 200-foot long section of the shore has a maximum elevation above the lake approximately 1.2 feet lower than the elevation of the dam crest. Thus, a 200-foot section of the lake will be overtopped by high water levels before the dam is overtopped.

e. Downstream Channel

The downstream channel of Mishe-Mokwa Dam is a narrow lake (Ballinger Lake) with no significant obstructions, although some debris was observed in the stilling basin area. Both banks are moderately steep and wooded and support residential development. In the vicinity of the dam, the lake is wider than it is further downstream forming a stilling basin for the spillway discharge.

SECTION 4: OPERATIONAL PROCEDURES

4.1 Procedures

The level of water in Lake Mishe-Mokwa normally is regulated naturally by discharge over the concrete weir sections of the spillway of Mishe-Mokwa Dam. Each spring, the stoplogs are removed in order to lower the lake for maintenance purposes. Reportedly, approximately one week is required to lower the lake 3 to 4 feet. During periods of low flow, water is pumped from the stilling basin to one of the upstream impoundments on the west side of the lake in order to recharge the lake volume. The level of water in the lake is further regulated by the series of embankments upstream of the main dam. Stoplog boards reportedly are not removed at times of intense storms.

4.2 Maintenance of the Dam

The dam generally is maintained by periodically replacing turf on the embankment where erosion has taken place. Also, the lake is lowered on an annual basis at which time the gate is repaired, the lake cleaned and docks repaired. There is no other program of regular inspection and maintenance; additional maintenance is performed as needed.

4.3 Maintenance of Operating Facilities

Maintenance of operating facilities, such as the recharge pump is performed as needed.

4.4 Description of Any Warning System in Effect

Reportedly, telephone communication is maintained between persons responsible for dams in the Medford Lakes area and the Civil Defense representatives in Medford Lakes Borough.

4.5 Evaluation of Operational Adequacy

The operation of the dam, together with the upstream embankments has been successful to the extent that the dam has not been overtopped since the present spillway was constructed.

Although maintenance documentation is poor, the adequacy of the maintenance program for the dam appears to have been fair. The spillway and roadway are in good condition. Some areas of maintenance have not been adequately performed, such as the following:

1. Trees and brush allowed to grow on downstream side of the embankment.
2. Erosion of embankment not adequately treated.
3. Deteriorated concrete of discharge culvert not repaired.
4. Bare soil on embankment allowed to remain without new grass.
5. Debris allowed to accumulate in stilling basin.

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. Design Data

The intensity of storm water runoff that the spillway should be able to handle is based on the size and hazard classification of the dam. This runoff intensity, called the spillway design flood (SDF), is described in terms of frequency or probable maximum flood (PMF) depending on the extent of the dam's size and potential hazard. According to the "Recommended Guidelines for Safety Inspection of Dams", published by the U.S. Army Corps of Engineers, the SDF for Mishe-Mokwa Dam falls in a range of $1/2$ PMF to PMF. In this case, the low end of the range, $1/2$ PMF, is chosen since the factors used to select size and hazard classification are on the low side of their respective ranges.

The SDF peak inflow calculated for Mishe-Mokwa Dam is 2031 cfs. This value is derived from the $1/2$ PMF hydrograph computed by the HEC-1-DB Flood Hydrograph Computer Program. Detailed hydrologic computations and computer output are contained in Appendix 4.

Discharge capacities for Mishe-Mokwa Dam were computed by considering two points of outflow from the lake: the spillway and the low area in the beach adjacent to the dam. The spillway was assumed to have the combined characteristics of a broad crested weir with breadth equal to 1 foot (concrete weir) and a sharp crested weir (stoplogs). The combined discharge with water level at

the dam crest was computed to be 160 cfs. The low area adjacent to the spillway was assumed to be a broad crested weir with $c=2.63$. Discharge over the low area with water level at the dam crest was computed to be 684 cfs.

In routing the SDF through the impoundment of the dam, the separate impoundments upstream of the main lake were considered to be one continuous lake. (See Appendix 4.) During a typical storm, these impoundments tend to attenuate the flow reaching the main lake. In routing the SDF, it was found that the dam would be overtopped by a depth of 0.5 foot over the dam crest and that the low area adjacent to the dam would be overtopped by a depth of 1.7 feet.

A breach analysis indicates that dam failure from overtopping would not significantly increase the hazard to loss of life downstream from the dam from that which would exist without overtopping failure. Accordingly, the subject spillway is assessed as being inadequate in accordance with criteria developed by the U.S. Army Corps of Engineers.

b. Experience Data

According to a member of the staff of the Medford Lakes maintenance department, the dam has not overtopped during the past 12 years nor has the low area of the lake adjacent to the dam been overtopped during that period of time. This experience tends to support the concept of an attenuative effect of the impoundments upstream from the main lake.

c. Visual Observations

No evidence was found at the time of inspection that would indicate previous overtopping of the dam or adjacent low area.

Two homes appear to be in the downstream flood plain of the low area adjacent to the dam, although an accurate determination of the limits of the flood plain cannot be made without further investigations. The homes are not in the flood plain of the dam and are not among those mentioned in paragraph 1.2.c. However, they could be effected by any overtopping of the low area (beach).

d. Overtopping Potential

As indicated in paragraph 5.1.a, a storm of magnitude equivalent to the SDF would cause overtopping of the dam to a height of 0.5 foot. Computations indicate that the dam can pass approximately 32 percent of the PMF without overtopping of the dam crest. In addition, the dam can pass approximately 8 percent of the PMF without overtopping of the low area (beach) adjacent to the dam.

SECTION 6: STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual observations

The embankment appeared, at the time of inspection, to be structurally stable with no evidence of cracks, displacement or differential settlement. However, the visual inspection disclosed two zones of seepage through the dam as described in paragraph 3.1.b.

An accurate determination of the severity of the seepage depends on several factors, one of which is periodic observation. The severity of the seepage noted at Mishe-Mokwa Dam cannot be precisely determined at the present time.

b. Design and Construction Data

The analysis of structural stability and construction data for the embankment are not available.

c. Operating Records

There are no operating records available for the dam. The water level of Lake Mishe-Mokwa is not monitored.

d. Post Construction Changes

Since the spillway was constructed at Mishe-Mokwa Dam in or about 1960, there have been few changes to the dam or the area surrounding it that could have any significant effect on its structural integrity. The only evidence

for the possibility of such a change is the existence of the bypass channel adjacent to the west side of the lake. The construction of the channel required excavation in the vicinity of the dam.

e. Seismic Stability

Mishe-Mokwa Dam is located in seismic Zone 1 as defined in "Recommended Guidelines for Safety Inspection of Dams" which is a zone of very low seismic activity. Experience indicates that dams in Seismic Zone 1 will have adequate stability under seismic loading conditions if stable under static loading conditions. Mishe-Mokwa Dam appeared to be stable at the time of inspection.

SECTION 7: ASSESSMENT AND RECOMMENDATIONS

7.1 Dam Assessment

a. Safety

Based on hydraulic and hydrologic analyses outlined in Section 5 and Appendix 4, the spillway of Mishe-Mokwa Dam is considered to be inadequate.

The structural integrity of the dam appears to be adequate based on field investigations; the seepage is not considered to be an immediate indication of instability. No reported nor written evidence was found that would contradict that assessment.

b. Adequacy of Information

Information was gathered from several sources, including:

1. field investigation, 2. USGS quadrangle sheet, 3. aerial photography from Burlington County, and 4. consultation with staff members of Medford Lakes maintenance department.

The information obtained is sufficient to allow a Phase I assessment as outlined in "Recommended Guidelines for Safety Inspection of Dams".

Some of the absent data are as follows:

1. Hydraulic and structural analyses of the dam and appurtenances.
2. Hydraulic data pertaining to the impoundments upstream of the main lake.
3. Stream and lake elevation gauging records.

4. Plans of the dam and appurtenances.
5. Description of the dam fill materials.
6. Inspection reports.

c. Necessity for Additional Data/Evaluation

Additional evaluation is considered necessary in order to assess the effect of the observed seepage on the structural integrity of the dam. The evaluation should be based on monitoring of the seepage as outlined in paragraph 7.2.c.

To provide an adequate record of existing conditions at the dam, a topographic survey should be undertaken as outlined in paragraph 7.2.c.

7.2 Recommendations

a. Remedial Measures

Based on hydraulic and hydrologic analyses outlined in paragraph 5.1.a., the spillway is considered to be inadequate. It is therefore recommended that a qualified professional engineer be engaged soon to perform more accurate hydraulic and hydrologic analyses relating to the spillway capacity. The analyses should more accurately determine runoff characteristics of the watershed, including the effect of the impoundments upstream of Lake Mishe-Mokwa and should refine the discharge capacity of the spillway and the downstream channel capacity.

Based on the findings of these analyses, the dam and spillway should be modified to prevent overtopping of the

dam resulting from a storm equivalent to the SDF. The following alternatives should be considered:

1. Improve the present spillway to accommodate the routed SDF flow rates.
2. Construct additional outlet facilities in the form of auxiliary spillways and emergency spillways.

Based on investigations made in connection with this report, it is evident that in the event that the low area (beach) adjacent to the dam is overtopped, two houses in its vicinity could be inundated. Remedial measures to correct this adverse condition should be initiated soon. Three alternative remedial measures are presented:

1. Improve the downstream channel of the low area to direct flow around the two homes.
2. Raise the crest of the low area in order to eliminate its overtopping. This alternative would necessitate a re-evaluation of the spillway adequacy.
3. Remove the homes in the downstream flood plain of the low area (beach).

It is further recommended that the following measures be undertaken by the owner in the near future.

1. Trees and brush on the dam embankment should be removed. Trees should be cut at the ground surface and brush removed in a way that will cause minimal disturbance to the embankment.

2. The eroded areas on the dam embankment should be properly filled and compacted. The drainage system for the road should be corrected to prevent future erosion. Such work should be done immediately after the trees and brush have been removed.
3. A good stand of grass should be established on all surfaces of the embankment.
4. The concrete spillway and discharge culvert should be thoroughly inspected and repaired as outlined below:
 - a. Drain the lake to an elevation equal to the invert of the stoplogs.
 - b. Sand blast all concrete and pressure grout any major cracks and patch all spalls and eroded surfaces.
 - c. Apply an epoxy preservative coating to all surfaces.
5. The stilling basin area should be cleaned of accumulated debris.

The implementation of the above measures will require proper detailed design and the obtaining of applicable DEP approvals.

b. Maintenance

The owner of the dam should initiate in the near future a program of periodic inspection and maintenance, the complete records of which to be kept on file and made available to the public. A visual inspection of the dam and appurtenances by a qualified professional engineer should be made annually and reported on a standardized

check-list form. Repairs should be made when required and the following maintenance should be performed annually: remove vegetation from the embankment, fill any eroded surfaces of the embankment and clear the downstream channel. In addition, the practice of lowering the lake annually for maintenance purposes should be continued and at least once every five years the submerged portions of the dam and spillway should be inspected and repaired while the lake is drawn down.

c. Additional Studies

Arrangements should be made soon to monitor the seepage by visual observation in order to determine its effect on the structural stability of the dam. If necessary, measurements should be made by the use of appropriate instrumentation. The monitoring should be performed on a monthly basis by a qualified professional engineer.

A detailed topographic survey of the dam and the areas around the dam should be undertaken in the near future by a qualified licensed land surveyor or professional engineer. The survey should become part of the permanent records of the dam mentioned in paragraph 7.2.b.

PLATES

MISHE - MOKWA DAM




PLATE I

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS

KEY MAP
MISHE - MOKWA DAM

I.D. N.J. 00419

SCALE: NONE

DATE: FEBRUARY, 1979




PLATE 2

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY


DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS VICINITY MAP MISHE - MOKWA DAM

I.D.N.J. 00419

SCALE: AS SHOWN

DATE: FEBRUARY, 1979



Note: Information taken from Rutgers University Soil Survey of New Jersey, Report No. 20 and Geologic Map of New Jersey prepared by Lewis and Kummel.

PLATE 3

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS


SOIL MAP

MISHE - MOKWA DAM

I.D. N.J. 00419


SCALE: NONE

DATE: FEBRUARY, 1979



NOTE:

Information taken from field inspection December 12, 1978.



MISHE - MOKWA
Elev. 70.3

PLATE 4

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS


GENERAL PLAN

MISHE - MOKWA DAM

I.D.N.J. 00419

SCALE: NOT TO SCALE

DATE: FEBRUARY, 1979



NOTE:

Information taken from field inspection December 12, 1978.





PLATE 5

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY


DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS
SPILLWAY PLAN & SECTION
MISHE - MOKWA DAM

I.D.N.J. 00419

SCALE: NOT TO SCALE

DATE: FEBRUARY, 1979



NOTE:
Information taken from field
inspection December 12, 1978.




PLATE 6

STORCH ENGINEERS
FLORHAM PARK, NEW JERSEY

DIVISION OF WATER RESOURCES
N.J. DEPT. OF ENVIR. PROTECTION
TRENTON, NEW JERSEY

INSPECTION AND EVALUATION OF DAMS

PHOTO LOCATION PLAN

MISHE - MOKWA DAM

I.D.N.J. 00419

SCALE: NOT TO SCALE

DATE: FEBRUARY, 1979

APPENDIX 1

Check List - Visual Inspection

Check List - Engineering Data

Check List
Visual Inspection
Phase 1

Name Dam Mishe-Mokwa County Burlington State N.J. Coordinators NJDEP

Date(s) Inspection 12/12/78 Weather Partly Cloudy Temperature 42°F

Pool Elevation at Time of Inspection 70.3 M.S.L. Tailwater at Time of Inspection 59.5 M.S.L.

Inspection Personnel:

R. McDermott

John Gribbin

Dinesh Patel

J. Gribbin Recorder

Present: Carl Goodfellow, Medford Lakes Borough maintenance staff.

CONCRETE/MASONRY DAMS

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|--------------|----------------------------|
| SEE PAGE ON LEAKAGE | N.A. | |
| STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS | N.A. | |
| DRAINS | N.A. | |
| WATER PASSAGES | N.A. | |
| FOUNDATION | N.A. | |

CONCRETE/MASONRY DAYS

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--------------------------------------|--------------|----------------------------|
| SURFACE CRACKS CONCRETE SURFACES | N.A. | |
| STRUCTURAL CRACKING | N.A. | |
| VERTICAL AND HORIZONTAL ALIGNMENT | N.A. | |
| MONOLITH JOINTS | N.A. | |
| CONSTRUCTION JOINTS | N.A. | |

EMBANKMENT

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|--|--|
| SURFACE CRACKS | None | |
| UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE | None | |
| SLOUGHING OR EROSION OF EMBANKMENT AND ADJUTANT SLOPES | Some erosion noted, especially on downstream face. | Leaning of fence posts along road on dam crest is not due to movement in the embankment. |
| VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST | Horiz. - slightly curved Vert. - level | Section of the lake shore southeast of dam approx. 1 foot lower than dam crest. Section is in a beach area and is approx. 200' long. |
| RIPRAP FAILURES | None observed | |

EMBANKMENT

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|---|--|----------------------------|
| GENERAL | Embankment is sandy with some grass on upstream face and grass, brush and trees on downstream face. | |
| JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM | Slight erosion at spillway. | |
| ANY NOTICEABLE SEEPAGE | Seepage observed at downstream toe of embankment, approx. 60' east of spillway. Seepage is slight and flows into a drainage ditch running parallel to toe of embankment. | |
| STAFF GAGE AND RECORDER | None | |
| DRAINS | N.A. | |

OUTLET WORKS

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|--|---|---|
| CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT | Concrete deteriorated at outlet end of arch culvert. (See Photo 7). | Outlet conduit (conc. arch culvert) serves for outlet works and spillway. |
| INTAKE STRUCTURE | Stoplogs in slot in upstream end of spillway Condition appeared to be satisfactory. | Stoplogs in spillway drop inlet serve as controlled weir portion of spillway and as outlet works. |
| OUTLET STRUCTURE | Same as outlet conduit. | |
| OUTLET CHANNEL | N.A. | |
| EMERGENCY GATE | Same as intake structure. | |

UNGATED SPILLWAY

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|-----------------------|--------------|----------------------------|
| CONCRETE WEIR | N.A. | |
| APPROACH CHANNEL | N.A. | |
| DISCHARGE CHANNEL | N.A. | |
| BRIDGE AND PIERS | N.A. | |

GATED SPILLWAY

| VISUAL EXAMINATION OF | OBSERVATIONS | REMARKS OR RECOMMENDATIONS |
|-------------------------------|---|---|
| CONCRETE SILL | Weir formed by sides of drop inlet in good condition. † | Spillway consists of uncontrolled conc. weir and controlled timber stop logs. (See OUTLET WORKS) |
| APPROACH CHANNEL | N.A. | |
| DISCHARGE CHANNEL | Discharge from spillway outflows through dam via concrete arch culvert. | |
| BRIDGE AND PIERS | N.A. | |
| GATES AND OPERATION EQUIPMENT | Timber stoplogs. (See OUTLET WORKS). | |

| INSTRUMENTATION | | | REMARKS OR RECOMMENDATIONS |
|-----------------------|--|--|----------------------------|
| VISUAL EXAMINATION | OBSERVATIONS | | |
| MONUMENTATION/SURVEYS | Bench mark on east end of spillway wall. | | Elev. = 73.24 |
| OBSERVATION WELLS | NONE | | |
| WEIRS | NONE | | |
| PIEZOMETERS | NONE | | |
| OTHER | N.A. | | |

RESERVOIR

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

SLOPES

Slopes range from less than 1% to 20% and average approx. 4%.

Dam crest is 2 feet higher than normal lake elevation. However, road adjacent to beach approx. 100 feet east of dam is 1 foot higher than normal lake elevation forming an overflow area.

SEDIMENTATION

Not Known

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

CONDITION

(OBSTRUCTIONS,
DEBRIS, ETC.)

Downstream channel is a narrow lake, wooded on both banks. No significant obstructions. (Name of lake: Ballinger Lake.) Residential development along both banks.

SLOPES

Side slopes of downstream channel are moderately steep (10% to 20%).

APPROXIMATE NO.
OF HOMES AND
POPULATION

Approx. 25 homes within 1600'. Height of homes above normal water level ranges from 2' to 10'.

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

| ITEM | REMARKS |
|----------------------------|---------------|
| PLAN OF DAM | Not Available |
| REGIONAL VICINITY MAP | Available |
| CONSTRUCTION HISTORY | Not Available |
| TYPICAL SECTIONS OF DAM | Not Available |
| HYDROLOGIC/HYDRAULIC DATA | Not Available |
| OUTLETS - PLAN | Not Available |
| - DETAILS | Not Available |
| -CONSTRAINTS | Not Available |
| -DISCHARGE RATINGS | Not Available |
| RAINFALL/RESERVOIR RECORDS | Not Available |

| ITEM | REMARKS |
|------|---------|
|------|---------|

| | |
|----------------|---------------|
| DESIGN REPORTS | Not Available |
|----------------|---------------|

| | |
|-----------------|---------------|
| GEOLOGY REPORTS | Not Available |
|-----------------|---------------|

| | |
|---|---------------|
| DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES | Not Available |
|---|---------------|

| | |
|---|---------------|
| MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD | Not Available |
|---|---------------|

| | |
|----------------------------------|---------------|
| POST-CONSTRUCTION SURVEYS OF DAM | Not Available |
|----------------------------------|---------------|

| | |
|----------------|---------------|
| BORROW SOURCES | Not Available |
|----------------|---------------|

| ITEM | REMARKS |
|---|---------------|
| MONITORING SYSTEMS | Not Available |
| MODIFICATIONS | Not Available |
| HIGH POOL RECORDS | Not Available |
| POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS | Not Available |
| PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS | Not Available |
| MAINTENANCE OPERATION RECORDS | Not Available |

ITEM

REMARKS

SPILLWAY PLAN

SECTIONS

Not Available

DETAILS

OPERATING EQUIPMENT
PLANS & DETAILS

Not Available

APPENDIX 2

Photographs




PHOTO 1
SPILLWAY




PHOTO 2
SPILLWAY GRATE AND STOPLOGS

12 DEC. 1978



PHOTO 3

SPILLWAY DISCHARGE CULVERT OUTLET,
DOWNSTREAM FACE OF EMBANKMENT.



PHOTO 4

SPILLWAY DISCHARGE CULVERT.




PHOTO 5

DISCHARGE STRUCTURE FOR BYPASS CHANNEL.



PHOTO 6

OUTLET FOR BYPASS CHANNEL.
PUMP FOR LOW FLOW RECHARGING.

12 DEC. 1978



PHOTO 7

CONCRETE DETERIORATION IN SPILLWAY DISCHARGE CULVERT.



PHOTO 8

DRAINAGE DITCH WITH SEEPAGE FLOW.

12 DEC. 1978



PHOTO 9
ROAD ON CREST OF DAM.




PHOTO 10
DOWNSTREAM CHANNEL,

12 DEC. 1978

APPENDIX 3

Engineering Data

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: Residential and wooded

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 70.3 (192 acre-feet)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): N.A.

ELEVATION MAXIMUM DESIGN POOL: 72.9

ELEVATION TOP DAM: 72.4 (Field measured)

SPILLWAY CREST: Concrete weir & timber stoplogs

- a. Elevation 70.1
- b. Type uncontrolled overflow
- c. Width 12 inches
- d. Length Total 15.6 feet
- e. Location Spillover Box inlet at upstream side of dam
- f. Number and Type of Gates One gate - timber stoplogs 2.4 feet long

OUTLET WORKS: 2.4 foot long slot in spillway

- a. Type Gate
- b. Location Upstream end of spillway
- c. Entrance inverts 61.9
- d. Exit inverts 61.5
- e. Emergency draindown facilities: Remove stoplogs

HYDROMETEOROLOGICAL GAGES: None

- a. Type N.A.
- b. Location N.A.
- c. Records N.A.

MAXIMUM NON-DAMAGING DISCHARGE:

(Lake stage equal to elev. 71.2) 42 c.f.s.

APPENDIX 4

Hydrologic Computations

STORCH ENGINEERS


Sheet 1 of

Project 1132

Made By JG Date 5/2/79

Mishe - Mokwa Dam

Chkd By Date



The impoundment of Mishe-Mokwa Dam consists of one main lake (elev. 70.3) and 7 upstream impoundments separated by road embankments and connected by discharge structures. Runoff from any storm is naturally routed through the upstream impoundments before reaching the dam. However, for simplicity, all 8 bodies of water will be considered to act as one lake.

STORCH ENGINEERS

Sheet 2 of

Project 1132

Made By KL Date 5-5-79

Mishe - McKong Dam

Chkd By JG Date 3/6/79

Size Classification

| | |
|----------------------------------|--------------|
| Surface area of main impoundment | 10 Ac \pm |
| Average depth of lake | 4 ft. |
| Structural height of dam | 12.9 ft. |
| Size classification | <u>Small</u> |

Hazard Potential Classification

| | |
|----------------------------------|-------------------|
| Number of inhabitable structures | approx. 25 |
| Hazard potential classification | high |
| Recommended SDF | $\frac{1}{2}$ PMF |

Hydrologic Analysis

The HEC -1-DB will be used to route the flood using
SCS triangular unit hydrograph with curvilinear transformation.
Drainage area = 0.83 sq. mi.

STORCH ENGINEERS

Sheet 3 of

Project 1132

Made By KL Date 2-5-79

Miche Mokwa Dam

Chkd By JG Date 3/6/79

Precipitation

(Re "Design of Small Dams" USDI, 1973)

From fig 15, Zone 6.

Probable Maximum Precipitation = 27 inches
for 6 hr. duration and 10 sq. mi. area.

| <u>Duration (hrs)</u> | <u>% PMP</u> |
|-----------------------|--------------|
| 6 | 100 |
| 12 | 109 |
| 24 | 117 |

Infiltration Data

Hydrologic soil group A

Land use $\frac{1}{2}$ urban $\frac{1}{2}$ woodlots

USE initial infiltration 1.5 inch

Constant infiltration 0.15 inch/hr.

STORCH ENGINEERS

Sheet 4 of

Project 1132

Made By RL Date 4-2-79

Mishe Hoking Dam

Chkd By Date

Time of concentration

Overland 1500' @ 1.5%

vel 0.35 fps

T 1.2 hrs

(Ref. SCS TR-55)

Channel 1800' @ 1.1%

vel 1.6 fps

T 0.3 hrs

$$T_c = 1.2 + 0.3 = 1.5 \text{ hrs}$$

Alternate method

Nomograph Pg 71 "Design of Small Dam"

$$L = 0.625 \text{ mi}$$

$$H = 42'$$

$$\begin{aligned} T_c &= 0.39 \text{ hr} \times 2.2 \text{ (adjustment factor)} \\ &= 0.86 \text{ hrs} \end{aligned}$$

$$\text{use } T_c = 1.2 \text{ hr}$$

$$\text{Lag} = 0.6 T_c$$

$$= 0.6 \times 1.2$$

$$\boxed{\text{Lag} = 0.72 \text{ hrs.}}$$

STORCH ENGINEERS

Sheet 5 of

Project 1132 Made By RL Date 6-2-79

Mishe Mokwa Dam Chkd By Date

Lake Storage Volume

Information from USGS & Aerial Photos

| | | | | |
|-------------------|--------|------|------|------|
| EL. (ft) | 62.0 * | 70.3 | 71.3 | 72.4 |
| Surface Area (Ac) | 0 | 48.0 | 57.6 | 70.5 |

*

Bottom of lake at spillway

HEC-1-DB program will develop storage

Capacity from surface area & elev.

STORCH ENGINEERS



Sheet 6 of

Project 1132


Made By RL Date 3-5-79

Mishe - Hekua Dam

Chkd By JG Date 3-6-79



SECTION A-A



SECTION B-B

STORCH ENGINEERS

Sheet 7 of Project 1132Made By RL Date 3-5-79Miche Mokuwa DamChkd By JG Date 3-6-79Elevation - Discharge Tabulation $L_1 = 2.4'$ effective length of stage 1 sharp crest weir $L_2 = 13.2'$ effective length of stage 2 broad crest weir $L_3 = 200'$ length of beach area C_1, C_2, C_3 coef. of discharge for L_1, L_2, L_3 respectively. $C_1 = 3.3$ $C_2 = 2.7$ to 3.3 $C_3 = 2.6$ Q_1, Q_2, Q_3 discharge over L_1, L_2, L_3 respectively. Q_{pipe} discharge thru $3.5' \times 3.5'$ culvertControlling Q_c will be the smaller value of Q_{pipe} vs $Q_1 + Q_2$ STAGE DISCHARGE TABULATION

| W.L. (ft) | h_1 (ft) | Q_1 (cfs) | h_2 (ft) | C_2 | Q_2 (cfs) | $Q_1 + Q_2$ (cfs) | Q_{pipe}^* (cfs) | Q_c (cfs) | h_3 (ft) | Q_3 (cfs) | $\Sigma Q = Q_2 + Q_c$ (cfs) |
|--------------|---------------|----------------|---------------|-------|----------------|----------------------|------------------------------|----------------|---------------|----------------|---------------------------------|
| 70.1 | 0 | 0 | - | - | 0 | 0 | - | 0 | - | 0 | 0 |
| 70.2 | 0.1 | 0.3 | - | - | 0 | 0.3 | - | 0.3 | - | 0 | 0.3 |
| 70.4 | 0.3 | 1.3 | 0.1 | 2.7 | 1.1 | 2.4 | - | 2.4 | - | 0 | 2.4 |
| 70.6 | 0.5 | 2.8 | 0.3 | 2.7 | 5.9 | 9 | - | 9 | - | 0 | 9 |
| 70.8 | 0.7 | 4.6 | 0.5 | 2.7 | 13 | 18 | - | 18 | - | 0 | 18 |
| 71.0 | 0.9 | 6.6 | 0.7 | 2.8 | 22 | 29 | 150 | 29 | - | 0 | 29 |
| 71.2 | 1.1 | 9.1 | 0.9 | 2.9 | 33 | 42 | - | 42 | 0 | 0 | 42 |
| 71.4 | 1.3 | 12 | 1.1 | 3.0 | 46 | 58 | - | 58 | 0.2 | 47 | 105 |
| 71.6 | 1.5 | 15 | 1.3 | 3.1 | 61 | 76 | - | 76 | 0.4 | 132 | 208 |
| 71.8 | 1.7 | 18 | 1.5 | 3.2 | 78 | 96 | 169 | 96 | 0.6 | 242 | 338 |
| 72.0 | 1.9 | 21 | 1.7 | 3.3 | 97 | 118 | - | 118 | 0.8 | 372 | 490 |
| 72.2 | 2.1 | 24 | 1.9 | 3.3 | 114 | 138 | - | 138 | 1.0 | 520 | 658 |
| 72.4 | 2.3 | 27 | 2.1 | 3.3 | 133 | 160 | 182 | 160 | 1.2 | 684 | 844 |
| 72.6 | 2.5 | 31 | 2.3 | 3.3 | 160 | 191 | 196 | 196 | 2.8 | 2436 | 2632 |

* See Highway Culvert Charts.

STORCH ENGINEERS

Sheet 8 of


Project 1132

Made By RL Date 3-5-79

Mishe Mokwa Dam

Chkd By JG Date 3-6-79

STAGE DISCHARGE CURVE



STORCH ENGINEERS

Sheet 9 of


Project 1132

Made By JG Date 4-2-79

Mishe - Mokwa Dam

Chkd By Date

OVERTOPPING POTENTIAL



Overtopping of low area occurs at elev. 71.2
with $Q = 42$ c.f.s. ($\sim 8\%$ PMF)

Overtopping of dam occurs at elev. 72.4 with
 $Q = 844$ c.f.s. ($\sim 32\%$ PMF)

STORCH ENGINEERS

Sheet _____ of _____

Project 1132


Made By JG Date 4-4-79

Mishe-Mokwa Dam


Chkd By _____ Date _____

BREACH ANALYSIS

Assume breach begins to develop when
reservoir stage reaches elev. 72.4 (top of dam).
Time to fully develop = 1.0 hr.



FULLY DEVELOPED BREACH



STORCH ENGINEERS


Sheet _____ of _____

Project 1132

Made By JG Date 4-4-79

Mishe - Makwa Dam

Chkd By _____ Date _____



CROSS SECTION
END OF REACH 1

$S=0.001$

STORCH ENGINEERS


Sheet _____ of _____

Project 1132

Made By JG Date 4-4-79

Mishe - Mokwa Dam

Chkd By _____ Date _____



HEC-1-DB COMPUTATIONS

A1 NATIONAL DAM SAFETY PROGRAM
 A2 MISME MOKWA DAM NEW JERSEY
 A3 MULTI RATIO PMF ROUTING

[illegible]

RUN DATE# 79/04/02.
TIME# 10.41.34.

NATIONAL DAM SAFETY PROGRAM
MISHE MOKWA DAM NEW JERSEY
MULTI-RATIO-PMF-ROUTING

| JOB SPECIFICATION | | IPLT | | INSTAN | |
|-------------------|-----|-------|-----|--------|-------|
| NG | NHR | IDAY | IHR | IMIN | METRC |
| 150 | 0 | 5 | 0 | 0 | 0 |
| | | JOPER | NWT | LROPT | TRACE |
| | | 5 | 0 | 0 | 0 |

| | | | | | |
|-------------------------------------|-----|-----|-----|-----|-----|
| RTIOS= | .50 | .40 | .30 | .20 | .10 |
| MULTI-PLAN ANALYSES TO BE PERFORMED | | | | | |
| NPLAN= 1 NRTIO= 5 LRTIO= 1 | | | | | |

[illegible]

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH TO MISHE MOKWA LAKE

| ISTAG | ICOMP | IECON | ITAPE | JPLT | JPRT | INAME | ISTAGE | IAUTO |
|-------|-------|-------|-------|------|------|-------|--------|-------|
| LAKE | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 |

| HYDROGRAPH DATA | | RATIO | | ISAME | | LOCAL | |
|-----------------|-------|-------|-------|-------|-------|-------|-------|
| INVDG | TAKEA | SNAP | TRSDA | TRSPC | ISNOV | ISNOV | ISNOV |
| 1 | .83 | 0.00 | .83 | 0.00 | 0 | 0 | 0 |
| 2 | | | | | | | |

| PLCIP DATA | | | |
|------------|-------|--------|--------|
| SPEL | PMS | R6 | R24 |
| 0.00 | 26.50 | 100.00 | 117.00 |
| | | | R96 |
| | | | R72 |
| | | | 0.00 |
| | | | 0.00 |

| LOSS DATA | | | | | | | | | | |
|-----------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| LRPT | STKR3 | DLTKR | RTIOL | ERAIN | STKR5 | RTIOK | STATL | CNSTL | ALSNX | RTIMP |
| 0 | 0.00 | 0.00 | 1.00 | 0.00 | 0.00 | 1.00 | 1.50 | .15 | 0.00 | 0.00 |

UNIT HYDROGRAPH DATA
TC= 0.00 LAG= .72

```
RECESSION DATA
STRTQ= -1.00  QRCSE= -.05  RTIOR= 2.00
```

| UNIT HYDROGRAPH 45 | END OF PERIOD | ORDINATES, TC= | 0.00 HOURS, LAG= | .72 VOL= 1.00 |
|--------------------|---------------|----------------|------------------|---------------|
| 19. | 62. | 19. | 29. | 51. |
| 18. | 61. | 19. | 29. | 51. |
| 17. | 60. | 19. | 29. | 51. |
| 16. | 59. | 19. | 29. | 51. |
| 15. | 58. | 19. | 29. | 51. |
| 14. | 57. | 19. | 29. | 51. |
| 13. | 56. | 19. | 29. | 51. |
| 12. | 55. | 19. | 29. | 51. |
| 11. | 54. | 19. | 29. | 51. |
| 10. | 53. | 19. | 29. | 51. |
| 9. | 52. | 19. | 29. | 51. |
| 8. | 51. | 19. | 29. | 51. |
| 7. | 50. | 19. | 29. | 51. |
| 6. | 49. | 19. | 29. | 51. |
| 5. | 48. | 19. | 29. | 51. |
| 4. | 47. | 19. | 29. | 51. |
| 3. | 46. | 19. | 29. | 51. |
| 2. | 45. | 19. | 29. | 51. |
| 1. | 44. | 19. | 29. | 51. |

PMF INFLOW HYDROGRAPH

| MO.DA | HR.MN | PERIOD | RAIN | EXCS | LOSS | COMP Q |
|-------|-------|--------|------|------|------|--------|
| 1.01 | 12.05 | 145 | .18 | .16 | .01 | 93. |
| 1.01 | 12.10 | 145 | .18 | .16 | .01 | 102. |
| 1.01 | 12.15 | 147 | .18 | .16 | .01 | 120. |
| 1.01 | 12.20 | 148 | .18 | .16 | .01 | 149. |
| 1.01 | 12.25 | 149 | .18 | .16 | .01 | 193. |
| 1.01 | 12.30 | 150 | .18 | .16 | .01 | 252. |
| 0.00 | 0.00 | 151 | .18 | .16 | .01 | 323. |
| 0.00 | 0.00 | 152 | .18 | .16 | .01 | 400. |
| 0.00 | 0.00 | 153 | .18 | .16 | .01 | 479. |
| 0.00 | 0.00 | 154 | .18 | .16 | .01 | 557. |
| 0.00 | 0.00 | 155 | .18 | .16 | .01 | 630. |
| 0.00 | 0.00 | 156 | .18 | .16 | .01 | 698. |
| 0.00 | 0.00 | 157 | .21 | .20 | .01 | 758. |
| 0.00 | 0.00 | 158 | .21 | .20 | .01 | 811. |
| 0.00 | 0.00 | 159 | .21 | .20 | .01 | 856. |
| 0.00 | 0.00 | 160 | .21 | .20 | .01 | 897. |
| 0.00 | 0.00 | 161 | .21 | .20 | .01 | 935. |
| 0.00 | 0.00 | 162 | .21 | .20 | .01 | 972. |
| 0.00 | 0.00 | 163 | .21 | .20 | .01 | 1009. |
| 0.00 | 0.00 | 164 | .21 | .20 | .01 | 1043. |
| 0.00 | 0.00 | 165 | .21 | .20 | .01 | 1076. |
| 0.00 | 0.00 | 166 | .21 | .20 | .01 | 1106. |
| 0.00 | 0.00 | 167 | .21 | .20 | .01 | 1133. |
| 0.00 | 0.00 | 168 | .21 | .20 | .01 | 1157. |
| 0.00 | 0.00 | 169 | .27 | .25 | .01 | 1179. |
| 0.00 | 0.00 | 170 | .27 | .25 | .01 | 1200. |
| 0.00 | 0.00 | 171 | .27 | .25 | .01 | 1220. |
| 0.00 | 0.00 | 172 | .27 | .25 | .01 | 1243. |
| 0.00 | 0.00 | 173 | .27 | .25 | .01 | 1268. |
| 0.00 | 0.00 | 174 | .27 | .25 | .01 | 1297. |
| 0.00 | 0.00 | 175 | .27 | .25 | .01 | 1329. |
| 0.00 | 0.00 | 176 | .27 | .25 | .01 | 1362. |
| 0.00 | 0.00 | 177 | .27 | .25 | .01 | 1395. |
| 0.00 | 0.00 | 178 | .27 | .25 | .01 | 1427. |
| 0.00 | 0.00 | 179 | .27 | .25 | .01 | 1456. |
| 0.00 | 0.00 | 180 | .27 | .25 | .01 | 1483. |
| 0.00 | 0.00 | 181 | .16 | .15 | .01 | 1504. |
| 0.00 | 0.00 | 182 | .32 | .31 | .01 | 1521. |
| 0.00 | 0.00 | 183 | .32 | .31 | .01 | 1535. |
| 0.00 | 0.00 | 184 | .48 | .47 | .01 | 1550. |
| 0.00 | 0.00 | 185 | .56 | .55 | .01 | 1573. |
| 0.00 | 0.00 | 186 | 1.37 | 1.36 | .01 | 1628. |
| 0.00 | 0.00 | 187 | 2.26 | 2.24 | .01 | 1758. |
| 0.00 | 0.00 | 188 | .37 | .37 | .01 | 1973. |
| 0.00 | 0.00 | 189 | .56 | .55 | .01 | 2265. |
| 0.00 | 0.00 | 190 | .48 | .47 | .01 | 2634. |
| 0.00 | 0.00 | 191 | .32 | .31 | .01 | 3058. |
| 0.00 | 0.00 | 192 | .32 | .31 | .01 | 3462. |
| 0.00 | 0.00 | 193 | .25 | .23 | .01 | 3779. |
| 0.00 | 0.00 | 194 | .25 | .23 | .01 | 3979. |
| 0.00 | 0.00 | 195 | .25 | .23 | .01 | 4062. |
| 0.00 | 0.00 | 196 | .25 | .23 | .01 | 4039. |
| 0.00 | 0.00 | 197 | .25 | .23 | .01 | 3914. |
| 0.00 | 0.00 | 198 | .25 | .23 | .01 | 3726. |
| 0.00 | 0.00 | 199 | .25 | .23 | .01 | 3490. |
| 0.00 | 0.00 | 200 | .25 | .23 | .01 | 3216. |
| 0.00 | 0.00 | 201 | .25 | .23 | .01 | 2942. |
| 0.00 | 0.00 | 202 | .25 | .23 | .01 | 2706. |
| 0.00 | 0.00 | 203 | .25 | .23 | .01 | 2508. |
| 0.00 | 0.00 | 204 | .25 | .23 | .01 | 2345. |
| 0.00 | 0.00 | 205 | .19 | .18 | .01 | 2210. |
| 0.00 | 0.00 | 206 | .19 | .18 | .01 | 2094. |
| 0.00 | 0.00 | 207 | .19 | .18 | .01 | 1991. |
| 0.00 | 0.00 | 208 | .19 | .18 | .01 | 1899. |
| 0.00 | 0.00 | 209 | .19 | .18 | .01 | 1818. |
| 0.00 | 0.00 | 210 | .19 | .18 | .01 | 1740. |
| 0.00 | 0.00 | 211 | .19 | .18 | .01 | 1668. |
| 0.00 | 0.00 | 212 | .19 | .18 | .01 | 1601. |
| 0.00 | 0.00 | 213 | .19 | .18 | .01 | 1540. |
| 0.00 | 0.00 | 214 | .19 | .18 | .01 | 1485. |
| 0.00 | 0.00 | 215 | .19 | .18 | .01 | 1436. |
| 0.00 | 0.00 | 216 | .01 | .00 | .01 | 1393. |
| 0.00 | 0.00 | 217 | .01 | .00 | .01 | 1352. |
| 0.00 | 0.00 | 218 | .01 | .00 | .01 | 1310. |
| 0.00 | 0.00 | 219 | .01 | .00 | .01 | 1263. |
| 0.00 | 0.00 | 220 | .01 | .00 | .01 | 1207. |
| 0.00 | 0.00 | 221 | .01 | .00 | .01 | 1136. |
| 0.00 | 0.00 | 222 | .01 | .00 | .01 | 1050. |
| 0.00 | 0.00 | 223 | .01 | .00 | .01 | 953. |
| 0.00 | 0.00 | 224 | .01 | .00 | .01 | 851. |
| 0.00 | 0.00 | 225 | .01 | .00 | .01 | 747. |
| 0.00 | 0.00 | 226 | .01 | .00 | .01 | 646. |
| 0.00 | 0.00 | 227 | .01 | .00 | .01 | 551. |
| 0.00 | 0.00 | 228 | .01 | .00 | .01 | 464. |
| 0.00 | 0.00 | 229 | .01 | .00 | .01 | 387. |
| 0.00 | 0.00 | 230 | .01 | .00 | .01 | 321. |
| 0.00 | 0.00 | 231 | .01 | .00 | .01 | 268. |
| 0.00 | 0.00 | 232 | .01 | .00 | .01 | 225. |
| 0.00 | 0.00 | 233 | .01 | .00 | .01 | 198. |
| 0.00 | 0.00 | 234 | .01 | .00 | .01 | 185. |
| 0.00 | 0.00 | 235 | .01 | .00 | .01 | 172. |
| 0.00 | 0.00 | 236 | .01 | .00 | .01 | 161. |
| 0.00 | 0.00 | 237 | .01 | .00 | .01 | 150. |
| 0.00 | 0.00 | 238 | .01 | .00 | .01 | 140. |
| 0.00 | 0.00 | 239 | .01 | .00 | .01 | 131. |
| 0.00 | 0.00 | 240 | .01 | .00 | .01 | 122. |
| 0.00 | 0.00 | 241 | .01 | .00 | .01 | 114. |
| 0.00 | 0.00 | 242 | .01 | .00 | .01 | 106. |

END-OF-PERIOD HYDROGRAPH ORDINATES

[illegible]

| | 70 | 71 | 72 | 73 | 74 | 75 | 76 | 77 | 78 | 79 | 80 | 81 | 82 | 83 | 84 | 85 | 86 | 87 | 88 | 89 | 90 | 91 | 92 | 93 | 94 | 95 | 96 | 97 | 98 | 99 | 100 | 101 | 102 | 103 | 104 | 105 | 106 | 107 | 108 | 109 | 110 | 111 | 112 | 113 | 114 | 115 | 116 | 117 | 118 | 119 | 120 | 121 | 122 | 123 | 124 | 125 | 126 | 127 | 128 | 129 | 130 | 131 | 132 | 133 | 134 | 135 | 136 | 137 | 138 | 139 | 140 | 141 | 142 | 143 | 144 | 145 | 146 | 147 | 148 | 149 | 150 | 151 | 152 | 153 | 154 | 155 | 156 | 157 | 158 | 159 | 160 | 161 | 162 | 163 | 164 | 165 | 166 | 167 | 168 | 169 | 170 | 171 | 172 | 173 | 174 | 175 | 176 | 177 | 178 | 179 | 180 | 181 | 182 | 183 | 184 | 185 | 186 | 187 | 188 | 189 | 190 | 191 | 192 | 193 | 194 | 195 | 196 | 197 | 198 | 199 | 200 | 201 | 202 | 203 | 204 | 205 | 206 | 207 | 208 | 209 | 210 | 211 | 212 | 213 | 214 | 215 | 216 | 217 | 218 | 219 | 220 | 221 | 222 | 223 | 224 | 225 | 226 | 227 | 228 | 229 | 230 | 231 | 232 | 233 | 234 | 235 | 236 | 237 | 238 | 239 | 240 | 241 | 242 | 243 | 244 | 245 | 246 | 247 | 248 | 249 | 250 | 251 | 252 | 253 | 254 | 255 | 256 | 257 | 258 | 259 | 260 | 261 | 262 | 263 | 264 | 265 | 266 | 267 | 268 | 269 | 270 | 271 | 272 | 273 | 274 | 275 | 276 | 277 | 278 | 279 | 280 | 281 | 282 | 283 | 284 | 285 | 286 | 287 | 288 | 289 | 290 | 291 | 292 | 293 | 294 | 295 | 296 | 297 | 298 | 299 | 300 | 301 | 302 | 303 | 304 | 305 | 306 | 307 | 308 | 309 | 310 | 311 | 312 | 313 | 314 | 315 | 316 | 317 | 318 | 319 | 320 | 321 | 322 | 323 | 324 | 325 | 326 | 327 | 328 | 329 | 330 | 331 | 332 | 333 | 334 | 335 | 336 | 337 | 338 | 339 | 340 | 341 | 342 | 343 | 344 | 345 | 346 | 347 | 348 | 349 | 350 | 351 | 352 | 353 | 354 | 355 | 356 | 357 | 358 | 359 | 360 | 361 | 362 | 363 | 364 | 365 | 366 | 367 | 368 | 369 | 370 | 371 | 372 | 373 | 374 | 375 | 376 | 377 | 378 | 379 | 380 | 381 | 382 | 383 | 384 | 385 | 386 | 387 | 388 | 389 | 390 | 391 | 392 | 393 | 394 | 395 | 396 | 397 | 398 | 399 | 400 | 401 | 402 | 403 | 404 | 405 | 406 | 407 | 408 | 409 | 410 | 411 | 412 | 413 | 414 | 415 | 416 | 417 | 418 | 419 | 420 | 421 | 422 | 423 | 424 | 425 | 426 | 427 | 428 | 429 | 430 | 431 | 432 | 433 | 434 | 435 | 436 | 437 | 438 | 439 | 440 | 441 | 442 | 443 | 444 | 445 | 446 | 447 | 448 | 449 | 450 | 451 | 452 | 453 | 454 | 455 | 456 | 457 | 458 | 459 | 460 | 461 | 462 | 463 | 464 | 465 | 466 | 467 | 468 | 469 | 470 | 471 | 472 | 473 | 474 | 475 | 476 | 477 | 478 | 479 | 480 | 481 | 482 | 483 | 484 | 485 | 486 | 487 | 488 | 489 | 490 | 491 | 492 | 493 | 494 | 495 | 496 | 497 | 498 | 499 | 500 | 501 | 502 | 503 | 504 | 505 | 506 | 507 | 508 | 509 | 510 | 511 | 512 | 513 | 514 | 515 | 516 | 517 | 518 | 519 | 520 | 521 | 522 | 523 | 524 | 525 | 526 | 527 | 528 | 529 | 530 | 531 | 532 | 533 | 534 | 535 | 536 | 537 | 538 | 539 | 540 | 541 | 542 | 543 | 544 | 545 | 546 | 547 | 548 | 549 | 550 | 551 | 552 | 553 | 554 | 555 | 556 | 557 | 558 | 559 | 560 | 561 | 562 | 563 | 564 | 565 | 566 | 567 | 568 | 569 | 570 | 571 | 572 | 573 | 574 | 575 | 576 | 577 | 578 | 579 | 580 | 581 | 582 | 583</ |
|--|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-------|
|--|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-------|

| RATIO OF PMF | ELEVATION STORAGE OUTFLOW | INITIAL VALUE | | SPILLWAY CREST | | TOP OF DAM | | DURATION | | TIME OF | | TIME OF FAILURE HOURS |
|--------------------|---------------------------------|-----------------------------------|------------------------------|-----------------------------|---------------------------|-------------------|-------------------------|-------------------------|-------|---------|------|-----------------------------|
| | | MAXIMUM RESERVOIR W.S. ELEV | MAXIMUM DEPTH OVER DAM | MAXIMUM STORAGE AC-FT | MAXIMUM OUTFLOW CFS | OVER TOP HOURS | MAX OUTFLOW HOURS | MAX OUTFLOW HOURS | | | | |
| 50 | 72.87 | 70.10 | 0.00 | 70.10 | 130.0 | 72.40 | 263.0 | 2.25 | 15.75 | 0.00 | 0.00 | |
| 40 | 72.63 | 130.0 | 0.00 | 130.0 | 263.0 | 844.0 | 1.50 | 16.75 | 0.00 | 0.00 | | |
| 30 | 72.33 | | 0.00 | | | | 0.00 | 16.92 | 0.00 | 0.00 | | |
| 20 | 71.93 | | 0.00 | | | | 0.00 | 17.08 | 0.00 | 0.00 | | |
| 10 | 71.42 | | 0.00 | | | | 0.00 | 18.42 | 0.00 | 0.00 | | |

| RATIO OF PMF | MAXIMUM RESERVOIR W.S. ELEV | MAXIMUM DEPTH OVER DAM | MAXIMUM STORAGE AC-FT | MAXIMUM OUTFLOW CFS | DURATION OVER TOP HOURS | MAX OUTFLOW HOURS | TIME OF FAILURE HOURS |
|--------------------|-----------------------------------|------------------------------|-----------------------------|---------------------------|-------------------------------|-------------------------|-----------------------------|
| 50 | 72.87 | .47 | 298. | 1514. | 2.25 | 15.75 | 0.00 |
| 40 | 72.63 | .27 | 260. | 1147. | 1.50 | 16.75 | 0.00 |
| 30 | 72.33 | 0.00 | 254. | 777. | 0.00 | 16.92 | 0.00 |
| 20 | 71.93 | 0.00 | 232. | 440. | 0.00 | 17.08 | 0.00 |
| 10 | 71.42 | 0.00 | 206. | 113. | 0.00 | 18.42 | 0.00 |

AD-A068 674

NEW JERSEY STATE DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/2
NATIONAL DAM SAFETY PROGRAM. MISHE - MOKWA DAM (NJ 00419), DELA--ETC(U)
MAY 79 R J MCDERMOTT DACW61-78-C-0124

UNCLASSIFIED

2 OF 2

AD
A068674




END

DATE
FILMED

6-79

DDC



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

| NATIONAL DAM SAFETY PROGRAM | | | | | | | | | |
|-----------------------------------|------|-------|-----|------|---|---|---|---|--|
| MISHE MOKWA DAM NEW JERSEY | | | | | | | | | |
| 0.5 PMF BREACH DOWNSTREAM ROUTING | | | | | | | | | |
| | | | | | | | | | |
| A1 | 150 | 0 | 1 | 1 | 0 | 0 | 0 | 3 | |
| A2 | 0.5 | | | | | | | | |
| A3 | 0.5 | | | | | | | | |
| J1 | 0.5 | | | | | | | | |
| K1 | 0 | | | | | | | | |
| L1 | 0 | 25.5 | 109 | 0.83 | 0 | 1 | | | |
| M1 | 0 | 100 | 117 | 0.83 | 0 | 1 | | | |
| N1 | 0.72 | | | | | | | | |
| O1 | -1.0 | -0.05 | 2.0 | | | | | | |
| P1 | 0 | | | | | | | | |
| Q1 | 0 | | | | | | | | |
| R1 | 0 | | | | | | | | |
| S1 | 0 | | | | | | | | |
| T1 | 0 | | | | | | | | |
| U1 | 0 | | | | | | | | |
| V1 | 0 | | | | | | | | |
| W1 | 0 | | | | | | | | |
| X1 | 0 | | | | | | | | |
| Y1 | 0 | | | | | | | | |
| Z1 | 0 | | | | | | | | |
| AA1 | 0 | | | | | | | | |
| AB1 | 0 | | | | | | | | |
| AC1 | 0 | | | | | | | | |
| AD1 | 0 | | | | | | | | |
| AE1 | 0 | | | | | | | | |
| AF1 | 0 | | | | | | | | |
| AG1 | 0 | | | | | | | | |
| AH1 | 0 | | | | | | | | |
| AI1 | 0 | | | | | | | | |
| AJ1 | 0 | | | | | | | | |
| AK1 | 0 | | | | | | | | |
| AL1 | 0 | | | | | | | | |
| AM1 | 0 | | | | | | | | |
| AN1 | 0 | | | | | | | | |
| AO1 | 0 | | | | | | | | |
| AP1 | 0 | | | | | | | | |
| AQ1 | 0 | | | | | | | | |
| AR1 | 0 | | | | | | | | |
| AS1 | 0 | | | | | | | | |
| AT1 | 0 | | | | | | | | |
| AU1 | 0 | | | | | | | | |
| AV1 | 0 | | | | | | | | |
| AW1 | 0 | | | | | | | | |
| AX1 | 0 | | | | | | | | |
| AY1 | 0 | | | | | | | | |
| AZ1 | 0 | | | | | | | | |
| BA1 | 0 | | | | | | | | |
| BB1 | 0 | | | | | | | | |
| BC1 | 0 | | | | | | | | |
| BD1 | 0 | | | | | | | | |
| BE1 | 0 | | | | | | | | |
| BF1 | 0 | | | | | | | | |
| BG1 | 0 | | | | | | | | |
| BH1 | 0 | | | | | | | | |
| BI1 | 0 | | | | | | | | |
| BJ1 | 0 | | | | | | | | |
| BK1 | 0 | | | | | | | | |
| BL1 | 0 | | | | | | | | |
| BM1 | 0 | | | | | | | | |
| BN1 | 0 | | | | | | | | |
| BO1 | 0 | | | | | | | | |
| BP1 | 0 | | | | | | | | |
| BQ1 | 0 | | | | | | | | |
| BR1 | 0 | | | | | | | | |
| BS1 | 0 | | | | | | | | |
| BT1 | 0 | | | | | | | | |
| BU1 | 0 | | | | | | | | |
| BV1 | 0 | | | | | | | | |
| BW1 | 0 | | | | | | | | |
| BX1 | 0 | | | | | | | | |
| BY1 | 0 | | | | | | | | |
| BZ1 | 0 | | | | | | | | |
| CA1 | 0 | | | | | | | | |
| CB1 | 0 | | | | | | | | |
| CC1 | 0 | | | | | | | | |
| CD1 | 0 | | | | | | | | |
| CE1 | 0 | | | | | | | | |
| CF1 | 0 | | | | | | | | |
| CG1 | 0 | | | | | | | | |
| CH1 | 0 | | | | | | | | |
| CI1 | 0 | | | | | | | | |
| CJ1 | 0 | | | | | | | | |
| CK1 | 0 | | | | | | | | |
| CL1 | 0 | | | | | | | | |
| CM1 | 0 | | | | | | | | |
| CN1 | 0 | | | | | | | | |
| CO1 | 0 | | | | | | | | |
| CP1 | 0 | | | | | | | | |
| CQ1 | 0 | | | | | | | | |
| CR1 | 0 | | | | | | | | |
| CS1 | 0 | | | | | | | | |
| CT1 | 0 | | | | | | | | |
| CU1 | 0 | | | | | | | | |
| CV1 | 0 | | | | | | | | |
| CW1 | 0 | | | | | | | | |
| CX1 | 0 | | | | | | | | |
| CY1 | 0 | | | | | | | | |
| CZ1 | 0 | | | | | | | | |
| DA1 | 0 | | | | | | | | |
| DB1 | 0 | | | | | | | | |
| DC1 | 0 | | | | | | | | |
| DD1 | 0 | | | | | | | | |
| DE1 | 0 | | | | | | | | |
| DF1 | 0 | | | | | | | | |
| DG1 | 0 | | | | | | | | |
| DH1 | 0 | | | | | | | | |
| DI1 | 0 | | | | | | | | |
| DJ1 | 0 | | | | | | | | |
| DK1 | 0 | | | | | | | | |
| DL1 | 0 | | | | | | | | |
| DM1 | 0 | | | | | | | | |
| DN1 | 0 | | | | | | | | |
| DO1 | 0 | | | | | | | | |
| DP1 | 0 | | | | | | | | |
| DQ1 | 0 | | | | | | | | |
| DR1 | 0 | | | | | | | | |
| DS1 | 0 | | | | | | | | |
| DT1 | 0 | | | | | | | | |
| DU1 | 0 | | | | | | | | |
| DV1 | 0 | | | | | | | | |
| DW1 | 0 | | | | | | | | |
| DX1 | 0 | | | | | | | | |
| DY1 | 0 | | | | | | | | |
| DZ1 | 0 | | | | | | | | |
| EA1 | 0 | | | | | | | | |
| EB1 | 0 | | | | | | | | |
| EC1 | 0 | | | | | | | | |
| ED1 | 0 | | | | | | | | |
| EE1 | 0 | | | | | | | | |
| EF1 | 0 | | | | | | | | |
| EG1 | 0 | | | | | | | | |
| EH1 | 0 | | | | | | | | |
| EI1 | 0 | | | | | | | | |
| EJ1 | 0 | | | | | | | | |
| EK1 | 0 | | | | | | | | |
| EL1 | 0 | | | | | | | | |
| EM1 | 0 | | | | | | | | |
| EN1 | 0 | | | | | | | | |
| EO1 | 0 | | | | | | | | |
| EP1 | 0 | | | | | | | | |
| EQ1 | 0 | | | | | | | | |
| ER1 | 0 | | | | | | | | |
| ES1 | 0 | | | | | | | | |
| ET1 | 0 | | | | | | | | |
| EU1 | 0 | | | | | | | | |
| EV1 | 0 | | | | | | | | |
| EW1 | 0 | | | | | | | | |
| EX1 | 0 | | | | | | | | |
| EY1 | 0 | | | | | | | | |
| EZ1 | 0 | | | | | | | | |
| FA1 | 0 | | | | | | | | |
| FB1 | 0 | | | | | | | | |
| FC1 | 0 | | | | | | | | |
| FD1 | 0 | | | | | | | | |
| FE1 | 0 | | | | | | | | |
| FF1 | 0 | | | | | | | | |
| FG1 | 0 | | | | | | | | |
| FH1 | 0 | | | | | | | | |
| FI1 | 0 | | | | | | | | |
| FJ1 | 0 | | | | | | | | |
| FK1 | 0 | | | | | | | | |
| FL1 | 0 | | | | | | | | |
| FM1 | 0 | | | | | | | | |
| FN1 | 0 | | | | | | | | |
| FO1 | 0 | | | | | | | | |
| FP1 | 0 | | | | | | | | |
| FQ1 | 0 | | | | | | | | |
| FR1 | 0 | | | | | | | | |
| FS1 | 0 | | | | | | | | |
| FT1 | 0 | | | | | | | | |
| FU1 | 0 | | | | | | | | |
| FV1 | 0 | | | | | | | | |
| FW1 | 0 | | | | | | | | |
| FX1 | 0 | | | | | | | | |
| FY1 | 0 | | | | | | | | |
| FZ1 | 0 | | | | | | | | |
| GA1 | 0 | | | | | | | | |
| GB1 | 0 | | | | | | | | |
| GC1 | 0 | | | | | | | | |
| GD1 | 0 | | | | | | | | |
| GE1 | 0 | | | | | | | | |
| GF1 | 0 | | | | | | | | |
| GG1 | 0 | | | | | | | | |
| GH1 | 0 | | | | | | | | |
| GI1 | 0 | | | | | | | | |
| GJ1 | 0 | | | | | | | | |
| GK1 | 0 | | | | | | | | |
| GL1 | 0 | | | | | | | | |
| GM1 | 0 | | | | | | | | |
| GN1 | 0 | | | | | | | | |
| GO1 | 0 | | | | | | | | |
| GP1 | 0 | | | | | | | | |
| GQ1 | 0 | | | | | | | | |
| GR1 | 0 | | | | | | | | |
| GS1 | 0 | | | | | | | | |
| GT1 | 0 | | | | | | | | |
| GU1 | 0 | | | | | | | | |
| GV1 | 0 | | | | | | | | |
| GW1 | 0 | | | | | | | | |
| GX1 | 0 | | | | | | | | |
| GY1 | 0 | | | | | | | | |
| GZ1 | 0 | | | | | | | | |
| HA1 | 0 | | | | | | | | |
| HB1 | 0 | | | | | | | | |
| HC1 | 0 | | | | | | | | |
| HD1 | 0 | | | | | | | | |
| HE1 | 0 | | | | | | | | |
| HF1 | 0 | | | | | | | | |
| HG1 | 0 | | | | | | | | |
| HH1 | 0 | | | | | | | | |
| HI1 | 0 | | | | | | | | |
| HJ1 | 0 | | | | | | | | |
| HK1 | 0 | | | | | | | | |
| HL1 | 0 | | | | | | | | |
| HM1 | 0 | | | | | | | | |
| HN1 | 0 | | | | | | | | |
| HO1 | 0 | | | | | | | | |
| HP1 | 0 | | | | | | | | |
| HQ1 | 0 | | | | | | | | |
| HR1 | 0 | | | | | | | | |
| HS1 | 0 | | | | | | | | |
| HT1 | 0 | | | | | | | | |
| HU1 | 0 | | | | | | | | |
| HV1 | 0 | | | | | | | | |
| HW1 | 0 | | | | | | | | |
| HX1 | 0 | | | | | | | | |
| HY1 | 0 | | | | | | | | |
| HZ1 | 0 | | | | | | | | |
| IA1 | 0 | | | | | | | | |
| IB1 | 0 | | | | | | | | |
| IC1 | 0 | | | | | | | | |
| ID1 | 0 | | | | | | | | |
| IE1 | 0 | | | | | | | | |
| IF1 | 0 | | | | | | | | |
| IG1 | | | | | | | | | |

SUMMARY OF DAM SAFETY ANALYSIS

| | | | | |
|---------|---------------------------------|--------------------------------------|---------------------------------------|-------------------------------------|
| 1 | ELEVATION STORAGE OUTFLOW | INITIAL VALUE 70.10 130. 0. | SPILLWAY CREST 70.10 130. 0. | TOP OF DAM 72.40 263. 844. |
|---------|---------------------------------|--------------------------------------|---------------------------------------|-------------------------------------|

| | | | | | | | |
|--------------------|----------------------------------|------------------------------|-----------------------------|---------------------------|-------------------------------|---------------------------------|-----------------------------|
| RATIO OF PMF | MAXIMUM RESERVOIR W.S.ELEV | MAXIMUM DEPTH OVER DAM | MAXIMUM STORAGE AC-FT | MAXIMUM OUTFLOW CFS | DURATION OVER TOP HOURS | TIME OF MAX OUTFLOW HOURS | TIME OF FAILURE HOURS |
| .50 | 72.64 | .24 | 280. | 4935. | .60 | 17.08 | 16.08 |

PLAN 1 STATION 1

| | | | |
|-------|---------------------|---------------------|---------------|
| RATIO | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS |
| .50 | 4710. | 65.2 | 17.17 |

PLAN 1 STATION 2

| | | | |
|-------|---------------------|---------------------|---------------|
| RATIO | MAXIMUM FLOW,CFS | MAXIMUM STAGE,FT | TIME HOURS |
| .50 | 4672. | 65.5 | 17.17 |

APPENDIX 5

Bibliography

1. "Recommended Guidelines for Safety Inspection of Dams," Department of the Army, Office of the Chief of Engineers, Washington, D.C. 20314.
2. Design of Small Dams, Second Edition, United States Department of the Interior, Bureau of Reclamation, United States Government Printing Office, Washington, 1973.
3. Holman, William W. and Jumikis, Alfreds R., Engineering Soil Survey of New Jersey, Report No. 20 Burlington County, Rutgers University, New Brunswick, N. J. 1953.
4. "Geologic Map of New Jersey" prepared by J. Volney Lewis and Henry B. Kummel, dated 1910 - 1912.
5. Urban Hydrology for Small Watersheds, Technical Release No. 55, Engineering Division, Soil Conservation Service, United States Department of Agriculture, January 1975.
6. Herr, Lester A., Hydraulic Charts for the Selection of Highway Culverts, U.S. Department of Transportation, Federal Highway Administration, 1965.
7. Safety of Small Dams, Proceedings of the Engineering Foundation Conference, American Society of Civil Engineers, 1974.